

Dump Hopper Retaining Wall Remediation



LOCATION:
Murrin Murrin – Northern Goldfields

CLIENT:
Minara Resources

DURATION:
3 months

PROJECT SCOPE

Ausdrill was engaged to stabilise the wing walls of a Sulphur handling dump hopper at the processing plant in the Northern Goldfields. The scope of works included the installation of 500m of BluGeo GRP60 anchors, 100m² Grid mesh, and 100m³ fibrecrete spraying. The limited access and harsh environment was challenging although the early pre-planning, input from both Ausdrill's HSEQ department and client's management plans allowed for a successful project to be delivered to an exceptional standard.

Ausdrill was also engaged to install a cyclonic anchor system to all buildings within the main accommodation camp facility on site. We installed 1,000 Model 88 duckbill anchors and secured to the chassis rail of each building to prevent any potential uplift.